



**NOTES:**

1. INSTALLATION TO BE IN ACCORDANCE WITH MN PLUMBING CODE.
2. WATERMAIN TAP SHUT-OFF VALVE AND METERS SHALL CONFORM TO WATR-2002.
3. PRESSURE VACUUM BREAKER TO BE INSTALLED 12 INCHES ABOVE OUTLET OF HIGHEST SERVICE ELEVATION.
4. PRESSURE VACUUM BREAKER MUST BE TESTED BY A LICENSED PRACTITIONER WHEN INSTALLED.
5. NO PUMPS OR BACK PRESSURE ON DOWNSTREAM SIDE OF PRESSURE VACUUM BREAKER.
6. PROVIDE A MINIMUM 12" CLEARANCE FROM BOTTOM OF BACKFLOW PREVENTION DEVICE FOR MAINTENANCE.
7. SERVICE SIZE BY ENGINEER.

	DRW: JAS	DATE: 2/22/16	<b>VAULT METER NON-POTABLE</b>	<b>STANDARD PLATE NO. WATR-2005</b>
	APP: CMD	DATE: 2/22/16		

NOT TO SCALE